L2-M2 · HANDSHAKE SIGNALS

Handshake signals

When MoRo meets a CNC station

1. **Request**
   MoRo asks the machine to take or give up the load.

2. **Ready**
   The machine answers that it is ready.

3. **Complete**
   After the handoff, a complete signal closes the exchange.

4. **Spot a stalled handshake**
   The exchange pauses and does not move on. At L2 you recognise it and escalate; the fix belongs to the technician (L3A).

Check both sides show ready before a handoff.