L2-M2 · HANDSHAKE SIGNALS

Handshake signals

When MoRo meets a CNC station

1. **Two systems, one exchange**
   Loading from or delivering to a CNC station, MoRo and the machine exchange a handshake.

2. **Signals confirm readiness**
   So neither system acts before the other is genuinely ready.

3. **Also completion and any error state**
   The same exchange confirms the handoff is complete and reports an error if there is one.

4. **Spot a stalled handshake**
   The exchange pauses and does not progress. You do not manage the sequence: recognize it and flag it.

Stalled? Flag it.