L1-M3 · STARTUP SEQUENCE

# Startup checklist

Before MoRo starts its work

1. **Look first**
   The path is clear and the sensors are unobstructed.

2. **Power on**
   MoRo runs its own diagnostic: battery charge, navigation calibration and safety systems.

3. **Wait for the ready state**
   Do not assign anything until MoRo reports the ready state.

4. **Then assign the mission**
   Assigning early is a common, avoidable cause of interrupted starts.

**Always in this order.**